

# Los Carneros Water District Recycled Water Pipeline Project


AWWA Fall Conference CA-NV Section
October 28, 2015

Andrew Hawksworth, P.E. – Carollo Engineers




#### Acknowledgements

- Los Carneros Water District
  - John Stewart President
  - LCWD Board Members
- Napa Sanitation District
  - Andrew Damron, P.E. Project Manager
  - Robin Gamble Holly Project Eng.
- Carollo Engineers
  - Tracy Clinton, P.E. Associate VP
  - Anne Prudhel, P.E. Project Manager



#### **LCWD Overview: Where is Los Carneros?**



#### **LCWD Overview: Personal Effort**


- Formed in 1978 to bring recycled water to the 5,000 acre community.
- Made up of volunteers
- Developed an assessment district
- Multiple Town Hall
- Land owner questionnaires
- Agreements with Napa Sanitation District



#### **LCWD Overview: Water Supply Problem**

- Groundwater levels are dropping
- Improve water quality for irrigation
- Offset surface water use in the summer months
- Loss of revenue from unplanted crops
- Eliminate the need to truck in potable and recycled water.
- Current Drought






#### **Project Overview: Project Design**


- 8.6 miles of 6"-20" recycled water pipe
  - Combination of FPVC and Bell & Spigot
- 115 parcels, (4,000 irrigated acres)
- Truck fill station
- Jack & Bore Crossing
- Pipe Bridge
- Only Utilities, 26" and 16" HP Gas (400 psi!)





# **Background: Project Area**





#### Design Challenges

- Earthquake
- **East Side Connection**
- ✓ A Few Others


#### Design Challenges: Napa Earthquake

- August 24, 2015
- Magnitude 6.0
- Epicenter was one mile south project site


Fault had been identified as inactive




#### Design Challenges: Napa Earthquake



#### **Design Challenges: East Side Connection**



#### **Design Challenges: East Side Connection**




14

## **Design Challenges: A Few Others**

- No road closures during harvest
- Location of meters
- 36 Culvert Crossings

arolloTemplateWaterWave.pptx



#### **Metering Technology: Installation**


- 105 meters, plus ability to add more at a later date.
- Turbo Series
- Badger High Resolution Encoder
- Itron Radio Based Endpoint
- Itron pole mounted receiver








## Metering Technology: Remote Reading



### **Metering Technology: Web Portal**



#### **Metering Technology: Web Portal**

#### Customer

- Notifications: text, e-mail, phone or direct mail
- Estimate of their bill
- View historical, current and projected water use
- Integration of rainfall and temperature data
- Set thresholds
- Export data in .csv format

#### **Utility**

- Analyze for leak detection and notification
- View customer data
- Export usage data
- Set thresholds and set alerts
- View abnormal usage / accounts violating threshold restrictions

#### **Project Overview: Funding**

- Recycled Water Planning Grant from State Water Resources Control Board (SWRCB) for 50 % of the Feasibility Study
- Grant/Loan funding from State Revolving Fund (SRF) and Proposition 1 for the design and construction.
- Parcel Assessment Fees
- Stanly Ranch Development Partnership
- Napa Sanitation District
- Two grants from the US Bureau of Reclamation for agriculture irrigation and energy efficiency.



## **Project Overview: Project Cost**

- Engineers Estimate: \$15.5 Million
- Low Bid: \$10.5 Million
- Notice to Proceed: March 2015
- Expected Completion: January 2016

Grants and Loan Relief:

\$5.6 Million



